

## Brock - test results - 1.25" turf with thatch (Astroturf)

System Description				Results				
Turf pile height	Turf Description	Brock Product	Infill	ASTM F355-A Gmax	EN14809 Vertical Deformation - mm	EN14808 Force Reduction	Deltec Field Tester - Energy Restitution	ASTM F355-E - H.I.C. 1.3m drop height
1.5"	1.5" - 74oz slit film with nylon thatch	PowerBase YSR	Zeofill (1.5lbs / sq. ft.) - DRY	90.5	8.4	66%	30%	724
			Zeofill (1.5lbs / sq. ft.) - WET	88.0	9.0	68%	30%	666